

Loyalhanna Watershed Association Upper Latrobe Passive Treatment Project

Addendum #1

August 4, 2009

Project Specifications Update

- Task G: Pond Liners
 - The integrity of the pond liners must be demonstrated. The contractor should perform a 48 hour test that shows liner competency.
 - The connection between the pond liners and trough may be done mechanically as long as all hardware is corrosion resistant. All bolts, nuts, and screws must be stainless steel
- Task E: Excess Cut Removal
 - LUPRD is able to take all excess cut made available
 - LUPRD will mobilize five tri-axle trucks full time (8 hr days)
 - Assuming 16 CY loads, 5 trucks, 1-hr roundtips, then:
 - 8,000 CY will take 13 days
 - 14,550 CY will take 23 days
 - *Revise Task E as follows:*
 - Eliminate 4,000 CY option
 - Maintain 8,000 CY option (loaded into LUPRD trucks), balance to contractor
 - Add option for ALL excess cut loaded into LUPRD trucks
- Bid Sheet will be revised at by August 12 to reflect Task # change and any others that arise

Corrections to Bidder's Meeting Statements

- Bob Hedin misspoke regarding the number of wetland plants. The number is 14,120 (Task K of the Construction Narrative).